SPELLMAN HIGH VOLTAGE ELECTRONICS CORPORATION



Spellman's XRB150PN600 Monoblock® X-Ray source is designed for OEM applications powering its internal X-Ray tube up to 150kV at 600W. Features like power factor correction, small package size and a standard analog and RS-232 digital interface simplify integrating this unit into your X-Ray system. Standard models are available with cone shaped beam geometry. Proprietary emission control circuitry provides excellent regulation of X-Ray tube current, along with outstanding stability performance.

TYPICAL APPLICATIONS

X-Ray Scanning: Bone Densitometry, Food Inspection, Security

SPECIFICATIONS

Tube Type:

Focal Spot:

X-Ray Characteristics:

Glass tube, Tungsten target, Be filter 0.5mm x 0.5mm (IEC 336) Beam Filter: 0.06" Ultem Beam Geometry: Cone, 18° ±1°

Input Voltage:

200-240Vac ±10%, 50/60Hz, 6.5A maximum

X-Ray Tube Voltage:

Nominal X-Ray tube voltage is adjustable between 70kV to 150kV

X-Ray Tube Current:

1.0mA to 4.0mA over specified tube voltage range

X-Ray Tube Power:

160W continuous, 600W peak Duty Cycle: 30 seconds on, 300 seconds off @ 600W peak

Voltage Regulation:

Line:	$\pm 0.1\%$ for a $\pm 10\%$ input line change of
	180 to 264Vac
Load:	±0.1% for a 1.0mA to 4.0mA load change
	600W maximum

Voltage Accuracy:

Voltage measured across the X-Ray tube is within ±2% of the programmed value

- Integrated HV Supply, Filament Supply, X-Ray **Tube, Beam Port and Control Electronics**
- Compact & Lightweight
- Power Factor Corrected
- Can be Mounted in Any Physical Orientation
- Analog Monitoring and Standard RS-232 Digital Interface

Voltage Risetime:

±1% in less than 300ms

Voltage Overshoot:

±10% during 300ms risetime

Voltage Ripple:

1% rms of rated voltage @ 10Hz to 1MHz

Current Regulation:

Line: ±0.1% from 180-264Vac

Load: ±0.5% @ 70kV-150kV, 1.0mA to 4.0mA

Current Accuracy:

Current measured through the X-Ray tube is within ±2% of the programmed value

Current Risetime:

±1% in less than 300ms

Arc Intervention:

4 arcs in 10 seconds with a 200ms quench = Shutdown

Filament Configuration:

Internal high frequency AC filament drive with closed loop filament emission control

Analog Interface:

0 to 5Vdc ground referenced signals

Digital Interface:

RS-232 interface.

Control Software:

A demo GUI for engineering evaluations will be provided for the RS-232 digital interface upon request.

Interlock/Signals:

A hardware interlock function is provided

Operating Temperature:

0°C to +40°C

Storage Temperature:

-40°C to +70°C

Humidity:

10% to 95% relative humidity, non-condensing

Cooling:

External fan required. 250cfm minimum to maintain an oil temperature of 55° C



Corporate Headquarters Hauppauge, New York USA +1-631-630-3000 FAX: +1-631-435-1620 e-mail: sales@spellmanhv.com

www.spellmanhv.com

128079-001 REV. G

Spellman High Voltage is an ISO 9001 and ISO 14001 registered company Copyright © 2010 Spellman High Voltage Electronics Corp.

Input Line Connector:

3 pin Phoenix Contact P/N 1829167

Analog Interface Connector:

10 pin Phoenix Contact P/N 1755503

Digital Interface Connector:

9 pin D connector, female

Grounding Point:

8-32 ground stud provided on chassis

Dimensions:

13.46" x 13.38" x 6.24" (341.89mm x 339.85mm x 158.50mm)

Weight:

66lbs (30kg)

Orientation:

Can be mounted in any orientation.

X-Ray Leakage:

Less than 100mR/hr at 1m distance, measured at 140kV, 3mA

AC INPUT POWER JB1 3 PIN PHOENIX CONTACT

PIN	SIGNAL	PARAMETERS
1	Line	Line
2	GND	Chassis Ground
3	Neutral	Neutral

RS-232 DIGITAL INTERFACE – JB16 9 PIN FEMALE D CONNECTOR

PIN	SIGNAL	PARAMETERS
1	Spare	N/C
2	Transmit	RS-232
3	Receive	RS-232
4	Spare	N/C
5	Signal Ground	Ground
6	Spare	N/C
7	Spare	N/C
8	Spare	N/C
9	Spare	N/C

ANALOG INTERFACE – JB15 10 PIN PHOENIX CONTACT

PIN	SIGNAL	PARAMETERS
1	X-Ray Signal	+12Vdc =Enable X-Ray, 0Vdc/open = Disable X-Ray, Zin=1k Ω
2	X-Ray Signal Return	Signal Return
3	N/C	N/C
4	kV Monitor	0 to 5Vdc = 0 to 175kV, Zout= $10k\Omega$
5	Signal Ground	Signal Ground
6	mA Monitor	0 to 5Vdc = 0 to 4.5mA, Zout= $10k\Omega$
7	Fault Signal	Open collector, High (Open) = No Fault, 35Vdc @10mA maximum
8	HV ON Lamp Relay n/o	Relay Normally Open, 50Vdc @ 1A maximum
9	HV ON Lamp Relay common	Relay Common, 50Vdc @ 1A maximum
10	HV ON Lamp Relay n/c	Relay Normally Closed, 50Vdc @ 1A maximum

LED INDICATORS

INDICATOR	SIGNAL NAME	CONDITION Illuminated When
LED 1	OT	Over temperature occurs
LED 2	ARC FLT	Arc fault occurs
LED 3	UV	Low kV occurs
LED 4	OV	High kV occurs
LED 5	UC	Low mA occurs
LED 6	OC	High mA occurs
LED 7	X-RAY ON	X-Rays are enabled
LED 8	PWR	Power is ON



Corporate Headquarters Hauppauge, New York USA +1-631-630-3000 FAX: +1-631-435-1620 e-mail: sales@spellmanhv.com

 WWW.Spellmanhv.com
 128079-001
 REV. G

 Spellman High Voltage is an ISO 9001 and ISO 14001
 registered company

 Copyright © 2010 Spellman High Voltage Electronics Corp.

SPELLMAN HIGH VOLTAGE ELECTRONICS CORPORATION

XRB150PN600

PAGE 3 OF 3

DIMENSIONS: in.[mm]





FRONT VIEW CONTROL ASSEMBLY

SIDE VIEW CONTROL ASSEMBLY

AIR EXHAUST



SIDE VIEW CONTROL ASSEMBLY

AIR INTAKE





TOP VIEW TANK





Corporate Headquarters Hauppauge, New York USA +1-631-630-3000 FAX: +1-631-435-1620 e-mail: sales@spellmanhv.com

 WWW.Spellmanhv.com
 128079-001
 REV. G

 Spellman High Voltage is an ISO 9001 and ISO 14001
 registered company

 Copyright © 2010 Spellman High Voltage Electronics Corp.